1	Risk Mitigation in PFI/PPP Project Finance: A framework Model
2	for Financiers' Bankability Criteria.
3	
4 5	Abstract:
6	Purpose: This study explores the perspectives of UK PFI financiers' regarding the bankability
7 8	of four critical risks (construction and completion risk, operations, supply and demand risk) in PPP projects.
9	
10 11	Design/methodology: The study adopts multiple case study methodology and leveraged in- depth Interviews, documentations and focus group discussions to investigate the phenomenon.
12	
13	Findings: Results from the study unravelled 36 suitable bankability criteria including
14	acceptable mitigation strategies for evaluating the four critical risks during PFI/PPP
15	financing appraisal.
16	
17	Research Limitations/Implication: The study examined only projects with similar nature
18 19	and selected from two sectors of the UK economy (Road and Education Sectors). The context of the study is also based on UK's PFI/PPP and Construction Industry, with other
20 21	geographical regions outside the context of this study.
22	Practical Implication: This study provides a less complicated but useful understanding of
23	how risks in PFI/PPP projects may be packaged in a bankable way to get the confidence of
24 25	project financiers. The study also addresses concerns of over quantification of risk analysis in DEL/DDD approvides and provides a velociable approach, useful for non-finance eviented DDD
25 26	practitionary
20	pracilioners.
28	Social Implication: This study addresses the social concerns of too much complexity and
29	ambiguity in PFI/PPP structuring especially regarding factors that could make a project
30	acceptable to lenders.
31	
32	Originality/Value: The study proposes a "Bankability and Risk Qualitative Framework",
33	which presents bankability information on critical risks in clear manner and represents
34	critical parameters for winning lenders' approval for financing PFI/PPP projects.
35	

Key Words: Private Finance Initiatives (PFI), Public Private Partnership (PPP), Lenders'
 perspectives, Bankability, Risks.

38 Introduction

39 A central issue for lenders in Private Finance Initiative and Public Private Partnerships 40 (PFI/PPP) contracts is the protection of project cash flows against risks and uncertainties. 41 According to Burke and Demirag (2015), one of the most significant threats to the feasibility 42 of PFI projects is the risk that the expected revenues might not be realised. Given the 43 potential negative impact of risks on lenders' financial investment in PPPs (Delmon, 2017), 44 bankability of projects (i.e. willingness of lenders to finance a project after due consideration of its 45 related risks and returns) therefore remains a central issue for PPP loan approval (Özdemir, 46 2015).

47 Whilst a number of studies have identified diverse risks in PFI/PPPs i.e. political risk, currency risk, 48 revenue risk, availability risk, performance risk among others (Lavasani et al., 2015; Yescombe, 2013; 49 Demirag et al., 2011; Loosemore and Cheung, 2015). Other recent studies have contributed on 50 critical success factors (CSFs) (Wibowo and Alfen, 2015; Osei-Kyei, and Chan, 2017; Liu et al., 51 2016); risk modelling, simulation and evaluation (Kokkaew and Wipulanusat, 2014; Boateng et 52 al., 2015; Valipour et al., 2016; Owolabi et al., 2018), including PPP mega projects (He et al., 2015; 53 Chan et al., 2018). However, despite the contributions of these existing studies, there is a 54 noticeable dearth of academic literature on financiers' perspectives to bankability of critical 55 risks (i.e. construction and completion risk, operations, supply and demand risk) during PPP 56 financial appraisals. According to Zou et al. (2008), critical risks in PPP are risk situations 57 that can give rise to one or more other project risk-factors; and they often rank high on 58 lenders' risk assessment ladder, due to their impact on the project success and revenue (Zhu 59 and Chua, 2018).

Although numerous risk-factors may be considered critical to the success of a PPP project (Xu et al., 2015; Osei-Kyei and Chan, 2015), the focus of this study is to examine project financiers' bankability assessment of four critical risks in PFI/PPP projects (i.e. construction and completion risk, operations, supply and demand risk), from financiers' perspective. The selection of the four critical risk-factors hinges on studies like Oyedele (2013) and Osei-Kyei and Chan (2015) who highlighted the critical role of effective risk evaluation and management at the construction and operational phases of PPPs. In addition, the selected
risk-factors have huge relevance for successful project completion, demand/market as well as
smooth operations of most PPPs.

69 Hence, this study continues and extends existing literature on credit risk, risk evaluation 70 and bankability assessment in PPPs. It diverges from previous literature which are largely 71 dominated by statistical methods, analytical models, and market methodologies. It presents 72 a purely qualitative mind-map tool for evaluating the bankability of four critical risks 73 (construction, operations, supply and demand risks) in PFI/PPP especially from financiers' 74 perspective. As such, the study contributes to knowledge within PPP academic literature by 75 providing day-to-day construction contractors, sub-contractors, SMEs and less statistically 76 inclined PPP practitioners with critical parameters for packaging bankable risks in PPP 77 financing proposals. The following objectives were identified for the study:

- To identify suitable bankability criteria and risk mitigation strategies for evaluating
 construction and completion risk, operations risk, supply risk and demand risks
 respectively during PPP financing appraisal.
- 81 2. To understand the rationales and contexts under which lenders bankability
 82 requirements varies across PFI projects.
- 83 3. To develop a qualitative framework that present instant glance at the bankability of
 84 risks in PFI/PPP loan applications.

The next section of the study reviews extant literature on PFI/PPP procurement including lenders' risk exposures in PPPs. Section three presents a description of the four-initial case study PFI/PPP projects investigated in the study, while section four presents the methodology. In the fifth section, the qualitative findings from the study and validation processes were presented, including the proposed "Bankability and Risk" qualitative framework. Whilst the sixth section discusses the overall results, the final section concludes the study.

pg. 3

92 Project Finance in PFI/PPP and Lenders' Risk Exposures

93 In recent years the most common application of project finance is the Public Private 94 Partnership (PPP) Scheme (Yescombe, 2013). Public Private Partnership has been described 95 as collaboration between public and private sectors to deliver public projects (Delmon, 2011). 96 According to Akintoye et al. (2003), the introduction of the UK version of PPP known as 97 Private Finance Initiative (PFI) emerged in November 1992 and contributed to the wider 98 acceptance of PPP globally. Private Finance Initiative (PFI) came against the backdrop of the 99 need to reverse the huge public-sector debt and perceived inefficiencies in the UK public 100 service (Oyedele, 2013). From the public sector's perspective, PFI offers government the 101 opportunity to utilise private sector funds, including its technical and managerial competence 102 to deliver infrastructures whilst ensuring equitable risk transfer among project parties (HM 103 Treasury, 1997). As such, risk management is believed to play a crucial role in PFI/PPP 104 arrangements.

Al-Bahar and Crandall (1990: p.534), defined risk as "the exposure to the chance of 105 106 occurrences of events adversely or favourably affecting project objectives as a consequence of 107 uncertainty." According to Smith et al. (2014), every project involves one form of risk or the 108 other. However, the amount of risk exposure for lenders in PPP contracts are enormous, 109 especially as many critical/important risk factors threaten project viability. For instance, 110 according to Demirag et al. (2011), the negative effect of construction and completion risk can 111 adversely impact on lenders' financial investments in PPPs. This is due to the high-risk 112 exposure of lenders' funds during projects' construction period (Lavasani et al., 2015). Since 113 most PPP projects are usually front-loaded in terms of huge loan drawdowns, lenders' 114 investment is most vulnerable at construction stage (Grimsey and Lewis, 2002; Hoffman, 115 2008). In addition, studies by Valipour et al. (2016), and Grimsey and Lewis (2002) also 116 suggested that, once a project commences operations, risks relating to the smooth running of 117 the project usually becomes the most important risks. Operational risks could be caused by 118 a number of factors, one of which may be incompetency in the maintenance regime of the 119 project. In the event of any performance failures on such project, statutory deductions would

be made from the project's cash flows (Oyedele, 2013), which brings more volatility to projectrevenue and loan repayments (Hoffman, 2008).

122 Moreover, risks relating to supply of raw materials to projects is another critical risk in PPPs. 123 As argued by Finnerty (2013), adequate supply of raw materials to projects is crucial at both 124 construction and operation stages as it ensures smooth project delivery and operations. As 125 such, any unplanned interruptions to a project's supply chain portend danger to successful 126 project completion, its continuous operations and predictability of project cash flows 127 (Hoffman, 2008). Additionally, demand risk is another major risk in PPPs, and it usually 128 emanate from absence of a reliable purchaser to buy sufficient volumes of a project's outputs 129 at profitable prices (Valipour et al., 2016). In most circumstances, demand risk, (which is also 130 referred to in other contexts as market risk, purchase risk, or demand risk) may plunge PPP 131 projects into revenue crisis, with adverse impact on Cash Flow Available for Debt Service 132 (CFADS) to lenders. Considering the likelihood of the above discussed critical risks and their 133 potential adverse effects on PFI/PPPs, determining bankability of risks must be the starting 134 point for lenders' during PFI/PPP financing appraisals. As such, earlier techniques for risk 135 and bankability assessment in PPP have relied on the use of experts' judgement among other 136 risk evaluation approaches. However, the last three decades (between years 1998-2013) have 137 seen more project financiers shift towards risk quantification techniques such as Monte Carlo 138 simulation, Decision Analysis, Scenario Models, Case-Base Models; including more recent 139 techniques like Fuzzy Synthetic Approach, Fuzzy Fault Tree method, Hybrid Fuzzy 140 Cybernetic Analytic etc. (Zhang, 2004; Akbiyikli, 2006; Ameyaw and Chan, 2015; Lavasani, 141 et al., 2015; Valipour et al., 2016; Owolabi et al., 2018) etc.

However, despite the seeming effectiveness of many quantitative models, protecting lender's investments in PPP projects remains shrouded in uncertainty. Bankability of projects is said to be contextual and differs based on nature of projects and associated risks (Rolstadås *et al.*, 2011). In addition, the financial crisis of 1992 and 2008 which led to the introduction and subsequent refinements of BASEL I and II banking regulations have exposed the weaknesses in banks' current practices of counterparty risk quantification and assessment, especially on 148 asset classes such as the PPPs (Please See Table 1 below for existing lenders' assessment 149 methods and regulations for PPP projects including their shortcomings). According to Perold 150 (2004) and Bertram et al. (2012), most studies on actuarial risk modelling suffer similar 151 shortcomings of over reliance on forecast variables, as against the reality of risk occurrence. 152 This is because; mathematical models do not take into consideration, contextual factors 153 influencing lenders bankability decisions. In addition, most risk models are incapable of 154 practically quantifying the probability of risk exposure (Rolstadås et al., 2011), and in many 155 cases, the application of risk model itself may constitute additional risk, especially where 156 weakness in the model leads to wrong decision (Bertram et al., 2012). Overall, current credit 157 risk evaluation practices of financiers have only created market opportunity for big-time 158 financial experts to exploit, at the expense of ordinary PPP contractors (and sub-contractors, 159 SMEs etc.) with limited capacity for high-level financial engineering at the pre-contract 160 phase. As a result, the need to address these neglected population of construction/PPP 161 practitioners becomes very germane.

162Table 1: Existing lenders' assessment criteria/techniques for PPP projects and their163shortcomings

164 Methodology

165 This study adopted "multiple-case study strategy" to explore lenders' perspectives on 166 bankability of critical risks (i.e. construction and completion risk, operations, supply and 167 demand risk) in PFI projects. The selected cases consisted four projects from road 168 infrastructure sector and another four in the education sector of the U.K economy. The first 169 phase of the case study exploration involved two PFI projects from the education sector. 170 Similarly, the study used two additional PPP projects from the education sector to compare 171 and validate the initial case studies. Using a similar approach to the earlier phase, the 172 second-phase of case study exploration also involved two PFI projects from UK's road sector, 173 with additional two road projects used for literal validation of the cases. Going further, it is 174 important to note that, the selection of PPP projects from UK's transport and education 175 sectors was based on Government's official data (Private Finance Initiative & Private Finance 176 2 Projects, 2017 Summary Data) which showed the two sectors among the top-four sectors 177 with the highest number operational PPP projects. As such, the selected sectors and projects 178 have huge relevance to a wide range of PPP audiences within the UK context and provided 179 easier access to data for the research team. However, whilst its' worth clarifying that, this 180 study has not compared PPP projects in the road sector with projects in education sector; the 181 two sectors were only used as contexts to investigate the research problem. Furthermore, the 182 PPP projects investigated were those where participants showed willingness and cooperation 183 to discuss and support the research team with documentary evidences. Going further, the 184 sampling strategy for case study selecting in this literature is purposive sampling. This 185 technique facilitated access to suitable participants, case study projects as well as less-186 sensitive loan documents under a non-disclosure and anonymity agreement. Instructively, 187 the selected sampling approach has been adopted in some existing PFI/PPP literatures such 188 as Grimsey and Lewis (2002), Meng and McKevitt (2011) and Oyedele (2013).

Four case studies were initially selected as the main-case studies for in-depth investigation. These comprised two PFI road projects – one located in Northern Ireland and the other in South West of England. The two school PFI projects selected include a library project in South East of England and a PFI school project in the Midlands. Another set of four projects were then used to validate findings from the four main case studies. These include, a PPP road project located in Wales, a DBFO road project in South West of England, BSF school project in North East of England and BSF school project in the South West of England respectively.

196 The field study commenced with a two-way research approach consisting unstructured 197 interviews and document analysis. Fifteen (15) individual interviews were conducted with 198 participants selected from UK-domiciled projects financiers', all with experiences in PFI 199 project financing averaged 13.5 years. The interview participants comprised three senior 200 credit analysts, one senior loan manager, three structured finance experts, four risk 201 managers and four investment bankers among others. The interview sessions were open-202 ended with participants freely commenting on what makes a project bankable from lenders 203 perspective. The information provided were then corroborated with less-sensitive project loan 204 documentations obtained from the lenders and the findings therein. Considering that PFI 205 loan appraisals often involve higher-level technical and statistical evaluations (actuarial risk 206 evaluations), the research team obtained loan reports containing a "Rule-Based Model" 207 approach to loan evaluation. Rule-based model, also known as "Judgement Scoring Model" 208 (Li et al., 2017), is the traditional credit scoring method often introduced by lenders at 209 intermediate stage of loan appraisals. This usually comes before the construction of rigorous 210 statistical models. With judgement scoring approach, participants were able to subjectively 211 assign numerical scores to important loan criteria, based on perceived significance towards 212 fulfilling bankability requirements. These scores were awarded by interview participants on 213 a scale of 1 to10, with 10 indicating = highest favourability and 1= indication, lowest 214 favourability of the criterion as a bankability factor. All the interview sessions lasted an 215 average of 248 mins. However, in order to further strengthen the external validity of the case 216 study findings, two new focus group discussions (FGD) involving 14-participants (drawn from 217 lending institutions), were carried out. The selection of participants followed a purposive 218 sampling approach and only financiers with prior PPP project finance experience were 219 approached via existing contact networks. The FDG participants also supported with useful 220 information on validation case studies (more details of focus group is found in the analysis 221 section).

222 Description of Selected Case Study PFI/PPP Projects

223 This section presents the main case study projects investigated in the study. The cases were 224 briefly described with focus on important features and nature of the projects. Results from 225 the case studies are presented in the next section.

226 Case Study X.Y.Z

227 PFI Road Project in Northern Ireland

This project is a 125km road project in Northern Ireland delivered using the PFI scheme. The project is valued at £250million and will be paid for under a unitary payment method. The

230 project was contracted under a 30year concession agreement in which a team of private sector

consortium was responsible for the design, build, finance and operate (DBFO) of the road. The project involved the upgrade of 20.5km of existing roads, construction of 12.1 km of new dual lane carriageway, construction of new bypass routes, provision of four grade-separated junctions, 2 over bridges and 2 underpasses. The closure of the central reserve crossovers in the immediate vicinity of graded junctions was also included in the project plan. Also included in the project is the upgrading of existing infrastructure such as drainage, surfacing, street lighting, signing, white lining and footways and many more.

238

239 Case Study A.P.R

240 PPP Link-Bridge in South West of England

241 This project is a 948-meter long link bridge in South West of England that serves its 242 surrounding environment. The project was procured using Public Private Partnership (PPP) 243 arrangement, in which private sector consortiums was responsible for the designing, build, 244 finance and operate (DBFO) the project. With the project valued at about £330 million, the 245 consortium runs the project as a shadow toll payment arrangement with government paying 246 the concessionaire, a determined rate based on actual road use, for a period to last for 30 247 years. As part of the contract, the project company will review the toll rate yearly. The construction phase of the project took a period of four years and the remaining 26 years of 248 249 operation will see the consortium responsible for the overall maintenance and repairs of the 250 link bridge.

251

252 Case Study Q.H.A

253 Library Project in South East of England

This project is a new central library procured using the PFI model under a 25-year concession agreement. Remuneration arrangement under this contract is through unitary charge payment, based on service availability and performance. The edifice, which is valued at £15million, stands on a 5000 sq. meter land mass. The project provides a wide range of quality library services to its' surrounding environment including delivery of cultural, educational and recreational resources, ICT facilities, learning center, conference rooms and exhibition spaces. The library project also parades a very efficient energy management system with its heating, cooling, lighting and ventilation systems, all developed in conformity withenvironmentally sustainable standards.

263

264 Case Study P.K.W

265 PFI School Project in the Midlands

266 This project is a secondary school project in the Midlands delivered using the PFI scheme. 267 The project was planned as a 30-year concession agreement that includes the design, build, 268 finance and operate (DBFO) of the facility throughout the project lifecycle under a unitary 269 charge payment arrangement. The school facility, which admits about 1500 pupils of 11 to 18 270 years of age, was built at a value of £24 million. The college is designed with much attention 271 to Information Communications and Technology (ICT) facilities, given its status as a 272 designated business and enterprise college. Asides the main educational facilities, the new 273 college also boasts leisure and sporting centre (incorporating a 25m four-lane swimming 274 pool), dance and drama studios, gymnasium, sports stadium, four multipurpose playing 275 courts and a learning resource centre.

276 Analysis of Findings from Case Studies

277

278 With the aid of thematic analytical technique, interview data transcripts and loan documents 279 from the four-initial case study projects were coded using Nvivo10. During the coding 280 exercise, the researcher was able to pinpoint and record various patterns or themes across 281 the dataset, resulting in the identification of different bankability criteria and risk mitigation 282 strategies. After painstaking sorting of data, the analysis uncovered 36 relevant bankability 283 criteria frequently used by lenders to evaluate the identified critical risks (supply risk, 284 construction, demand and operations risks), especially during financing appraisal (please see 285 Table 2 below). For each identified criterion, the study obtained the associated bankability 286 scores as assigned by interview participants through judgement scoring method. Other risk 287 mitigation strategies typically proposed by project sponsors to alleviate lenders' bankability 288 requirements were also identified and shown in column 2 of Table 2. In addition, the thematic 289 analysis also helped uncover various other sub-risk elements, which are usually associated 290 with the critical risks during due diligence appraisal (Please see Column 2 of Table 2 below). These sub-risk elements represent the different variants of the examined critical risks, and
in most cases, they add to the complexity of the risk evaluation execrcise. Kindly see Tables
283 below for key findings from case study PFI/PPP projects).

294

- Table 2: Rule-Based Model Scores for Lenders' Bankability Criteria Employed in the
 Case Study Projects.
- 297
- 298

Table 3: Risks and other Emerging Sub-Risk Components in PFI/PPP Projects.

299 Following the initial qualitative data analysis and findings, the study proceeded to validate 300 the extracted results with new data from additional focus group discussions. This validation 301 was necessary and aligns with the perspective of Yilmaz (2013, pp.321), who suggested that 302 "the credibility of a qualitative study is affected by the extent to which systematic data 303 collection procedures, multiple data sources, triangulation, etc. are used for producing 304 trustworthy data". Based on this conclusion, two new focus group discussions (FGD) were 305 conducted with another set of 14-participants (drawn from lending institutions), who were 306 selected through purposive sampling technique. As such, participants with prior PPP project 307 finance experience were carefully identified and approached using existing contacts in other 308 financial institutions different from the ones initially sampled. The first FGD consisted of 8 309 participants comprising; 3 Senior finance managers, 2 infrastructure loan managers and 3 310 risk analysts respectively. Similarly, the second FGD consisted 6 participants comprising; 4 311 credit risk managers and 2 structured finance analysts.

Going further, in order to validate the earlier case studies, in line with Yin (2017), the study also identified and examined four new case study PPP projects via convenience sampling method. This was made possible, by asking FGD participants to comment on past PPP projects which they have been involved. Hence, participants commented on four different PPP projects in which they have played significant roles especially during the dealpreparation stage. The four projects are currently in operation and delivered using the DBFO and BOT models respectively (See Table 4 below for description of the validation case 319 studies). During the FGDs, participants were encouraged to comment on their PPP 320 experiences and the data presented to them. Participants were also requested to evaluate 321 the relevance of earlier findings using their own experiences in project finance. The average 322 years of experience of the FGD participants in PFI projects is 8.3 years and both sessions 323 lasted a cumulative total of 95mins. The FGD sessions were tape-recorded and transcribed. 324 After careful reading of interview transcripts, the new data was thematically analysed to 325 identify similarities and correlations between existing data and the newly collated subjective 326 opinions of the FGD participants.

327 Table 4: Framework Validation using Four PPP Case Studies

Finally, haven established strong correlation between the initial findings and new FGD data, the study relied on the validated findings, to directly peer each risk factors (including their sub-risk elements) with corresponding mitigation strategies presented by sponsors and the associated bankability criteria that lenders were interested in. This information was then used to develop a qualitative framework for evaluating "Bankability of Critical Risks" in PPP funding proposals (Please See Fig.1 below).

334 Meanwhile, in order to ensure that the developed framework is in-line with the expectation 335 of PPP financiers, the risk and bankability-framework was sent back to eight (8) project 336 finance specialists (with between 5-12 years' experience in PPP transactions) within the UK 337 project finance industry. These practitioners were requested to confirm the relevance of the 338 framework in terms of its usefulness as a tool for quick bankability evaluation of critical risks 339 in PPPs. In their response via emails, all the experts contacted confirmed that the sequence 340 of treatments presented by the framework provides an easy-to-follow mind-map needed for 341 quick evaluation of the four investigated critical risks. Based on this feedback, the study 342 therefore presents a conceptual tool and bankability framework that is useful for everyday 343 construction-PPP practitioners in order to aid their understanding and decision-making 344 when considering PPP project financing.

346

347 Discussion of Findings

348 This section discusses findings from the investigated case study projects.

349 Supply risk and associated bankability criteria

350 Evidences from interviews and loan documentations, as indicated in Table 2 above, revealed 351 that supply risk is inherent in the eight cases examined in the study. As pointed out by some 352 of the interview participants, an important bankability criterion for lenders in examining 353 supply risk, is the existence of price hedge contract for project supplies (raw materials). This 354 is confirmed by evidences from Table 2, showing that lenders assigned high judgement-scores 355 (20 and above) to hedging of project supply prices across all the case studies (except for case 356 study P.K.W). The above view was encapsulated in the views of one of the participants who 357 argued that:

- 358 "In most cases, what happens is that lenders want project sponsors to ensure
 359 that strong pricing arrangement for inputs is in place to ensure predictability
- 360 of cash flows...and this is mostly done through supply price hedging"
- 361 (Participant 13, individual Interviews, April 3rd, 2018).

362 This opinion succinctly captures the view of Mills (2010) who both argued that supply price 363 hedging allows the SPV to purchase its storable raw materials in advance for a determined price and therefore avoids any sudden hike in price of inputs. According to Hoffman (2008), 364 365 with a hedging contract, the project company is able to pass the risks associated with 366 commodity price fluctuations to a third party (hedger). Further evidences from participants' 367 opinions as shown in Table 2, revealed that, another important criterion for assessing the 368 bankability of supply risk in PFI loan application is the existence of reliable and experienced 369 raw material supplier. Most participants consented to the significance of this criterion in 370 mitigating supply risk. This is reflected in Table 2, where the bankability scores in most of the case studies examined were higher than the minimum score (20), denoting its' importancefrom lenders point of view. As summarised with the views of one of the participants:

373 "You need a dependable long-term supplier for such type of projects when
374 evaluating supply risk in loan applications. It helps when contractors
375 maintain database of trusted suppliers (Participant 4, Individual Interview,
376 April 3rd, 2018).

The above perspectives confirm earlier studies such as Finnerty (2013) who argued that the need to ensure constant supply of adequate volumes of raw materials at affordable prices to projects is very essential in PPPs. Since the construction and operations of PFI projects are input dependent, any possibility that a project will not receive the required raw materials may lead to project collapse (Burke and Demirag, 2015).

382 Demand risk with associated bankability criteria

Evidences from the qualitative study, as represented in Table 2 above indicate that demand risk or traffic risk, as may be called in other contexts, was very crucial for consideration in the investigated cases studies. In examining demand risk in PFI loan applications, interviewees suggested that, the predictability of projected cash flows is essential for its bankability. The above table revealed high bankability scores for this criterion, across the case studies examined. As captured in the analysis of one of the participants:

389 "I must say that one of the factors that will sway lenders decision is the cash
390 flow profile of the project. Of course, every lender wants to lend to lucrative
391 businesses, and in that respect, sponsors have got to simply demonstrate how
392 viable their projects are from a commercial point of view" (Participant 15,
393 Individual Interview, April 25th, 2018).

The above perspective was emphasized in studies such as Burke and Demirag, (2015), Hoffman (2008), and Akbiyikli *et al.* (2006). According to Akbiyikli *et al.* (2006), one of the fundamental assumptions behind project financing via PFI/PPP is the ability of projects to make revenue and repay private investments. Finnerty (2013) argued that, identifying projects with strong revenue potential is crucial to lenders' financial propositions in project finance. This becomes necessary to guarantee optimum protection to depositors' funds being invested in projects by banks (Hoffman, 2008).

401 From the perspectives of most interview participants, the severity of demand risk in PPP 402 loan applications is often hinged on who is accepting the risk between the client (government) 403 and the project company. Evidences shown in Table 2 revealed that, for the PFI school 404 projects (cases Q.H.A and P.K.W), the client (public sector) pays the project SPV for using the 405 school facilities through monthly unitary charges, which are based on project's availability 406 and performance. As such, demand risk is minimised as long as the operational performance 407 of the project is kept at optimum (this explain why bankability scores are a bit low for long-408 term purchase contract). However, the situation is different if the context is a PFI toll road 409 projects. 410

411 Participants further argued that, the existence of Government guarantee in any PFI contract 412 would definitely convince lenders to back the loan. Results in Table 2 revealed that, in road 413 PFI projects bankability scores are very high (between 35 and 50). As encapsulated in the 414 analysis of one of the interviewees:

415 "Lenders will almost jump at a contract that has a credible government
416 guarantee backing, especially considering that most OECD nations have
417 reasonably strong sovereign credit ratings" (Participant 1, Individual
418 Interview, May 16th, 2018).

419 It is important to note here that, both unitary payment approach and government guarantee 420 arrangements, significantly improve project bankability by leveraging the sovereign credit 421 rating of the government. Both approaches mitigate lenders' revenue concerns by 422 guaranteeing reliable cashflow predictability and project revenue.

423

424 O& M risk with associated bankability criteria

425 Going by findings from the interviews and documentary evidences as reflected in Table 2, 426 operations and maintenance (O&M) risk is inherent in all the case studies examined in the 427 study. As reflected in the high bankability scores awarded across all the case studies 428 investigated (20–34), lenders will consider long-term O&M contract for evaluating operations 429 risk in loan applications. As summarized in the views of one of the participants:

- 430 "You definitely want to have long term operations and maintenance (O&M)
 431 contract with a reliable operator. However, there are times when lenders
 432 might be more comfortable with having an independent O&M contractor to
- 433 handle the project." (Participant 7, Individual Interview, May 2nd, 2018).

434 The above assertion supports studies such as Finnerty (2013), Meng, and McKevitt, (2011) 435 who both argued that, engaging a reliable but independent O&M contractor gives lenders 436 more assurances that, sponsors will not compromise the smooth operations of the facility for 437 obscure motives. Further findings from participants suggest that, the record of 438 accomplishment and overall competence of the O&M operator will be crucial to lenders' 439 financing decision. This goes further to confirm the high bankability scores awarded this 440 criterion by lenders, as reflected in Table 2, where bankability scores for O&M competence 441 in all case studies ranged from 20 to 35. As encapsulated in the views of one of the 442 participants:

443 444 "Banks will look at the technical competence, performance track record in similar PPP projects and financial strength of the O&M contracting 445 company. Sometimes, contractors' familiarity with the technology to be used
446 on the project may also be important especially in large projects" (Participant
447 14, Individual Interview, 25th, 2018).

This opinion supports Grimsey and Lewis (2002) who argued that once PPP projects moves to the operations phase, the failure or success of the project will largely depend on the competency during operations regime. According to Hoffman (2008), regardless of how well designed or constructed a project might be, the operator requires sufficient expertise and experience to run the project at the levels needed to generate cash flows.

453

454 Construction and completion risk with associated bankability criteria

Going by results from Table 2, construction and completion risk is inherent in all the eight case studies investigated. According to a unanimous view of participants, the larger and complex a project is, the higher the risks associated with construction and completion of such projects. Therefore, in order to examine the bankability of construction risk in a PFI loan application, financiers will look at the construction contractor's competence. This is reflected in the high bankability scores assigned across the eight cases (scores above minimum of 20), as shown in Table 2. One of the participants captured the entire perspectives by arguing that:

462 "You don't want to commit lenders funds, in the range of 70% to 80% of
463 project cost into the hands of an incompetent and inexperienced construction
464 contractor, who may not complete the job on time and within budget"
465 (Participant 5, Individual Interview, May 4th, 2018).

This assertion confirms studies such as Zhang (2004), Zhu and Chua (2018). As Zhu and Chua (2018) rightly puts it, the technical competence and record of accomplishment of construction contractor is key for evaluating completion risk in PFI projects. The construction stage of projects is considered most critical for financiers, considering that huge funds are committed and interests on loans are only capitalized (Demirag et al., 2011). Additionally, 471 further findings also revealed that lenders will require project sponsors to engage an 472 independent technical expert for technical due diligence on the business case. This confirms 473 results shown in Table 2 where evidences reveal high bankability scores the criterion, based 474 on lenders' perception. As summarised in the views of one of the participant:

- 475 "Project sponsors must engage the services of an independent technical
 476 consultant to give advice on the suitability of the project technology and the
 477 likely downside factors in the project" (Participant 11, Individual Interview,
- 478

June 1st, 2018).

479 Conclusion and Implication for Practice

480 This study examined the bankability of four critical risks in PFI/PPP projects namely; supply 481 risk, demand, O&M and construction risks respectively. Results from the study identified 36 482 relevant bankability criteria suitable for evaluating the identified risks, especially at the pre-483 contract phase of lenders' financing appraisal. The study also uncovered the subjective 484 importance of each factor/criterion as they influence the bankability decision of lenders using 485 'rule-based scoring approach'. Based on the findings from the study, it was evident that a key 486 success factor for getting lenders' support in PFI/PPP arrangements is to understand the 487 necessary bankability conditions motivating lenders. The results also showed that such 488 motivating factors are not entirely quantitative in nature but comprise other expert 489 judgement-based factors which has impact on bankability decisions. The result also revealed 490 the relative bias (as suggested by Pantelias & Roumboutsos, 2015) in the existing handling 491 of counter-party risk assessment of PPP lenders due to disproportionate on risk as the 492 construction phase as against risk in other important project phases. The over-reliance of 493 PPP lenders on projects backed by government (i.e. via unitary charge payment or 494 guarantees), as against projects structured on pure commercial basis, was also revealed in 495 this study. By offering incomplete information on factors driving counter-party risk 496 evaluation in PPPs, existing knowledge of project bankability may be deemed insufficient to 497 aid ordinary PPP practitioners. These findings have significant implications for potential 498 project sponsors and public-sector clients looking for long-term finance for critical

499 infrastructure projects. Considering the current apathy from lenders towards long-term, 500 limited-recourse projects, achieving bankability for PPP projects will be much less tedious, if 501 ordinary PPP contractors and potential sponsors approach their own internal project 502 evaluation from lenders' perspective, by relying on key factors that motivates lenders and 503 mitigate risk. Hence, the study advocates better understanding of critical parameters for 504 packaging bankable risks in project financing proposals in order to win lenders loan approval. 505 This is essential as evidences from several HM Treasury reports have shown that, many 506 laudable public-private projects have failed to materialise due to poor structuring of projects' 507 bankability and viability, thereby denying deserving communities of critical infrastructures, 508 as government cuts back on public spending. As such, if the UK government is to achieve her 509 target of 50% public-private project financing, out of the estimated £483 billion project 510 investment targeted by 2020-21, better understanding of structuring bankable projects with 511 well-mitigated risks, will be an important panacea.

512 In addition, findings from the study also indicated that bankability of risks in PPP is not 513 static but contextual, and often vary based on a number of prevailing factors important to 514 lenders. For instance, whilst a factor such as 'government guarantee support' may not raise 515 much concern for lenders in a PPP school project due to less complexity and scale. It is very 516 much likely to be an important bankability factor in a PPP toll-road project due to large scale 517 and capital-intensive nature of such projects, including the high-probability of revenue risk 518 or other country-related risk factors. Hence, lenders will attach much favourability to a 519 government guarantee-backed PPP project, as it reflects sovereign-support and assures 520 project revenue, including returns on investment. By implication, PPP promoters must 521 therefore be creative and pro-active with the project to ensure long-term commercial viability 522 and bankability of their projects. This will require constant re-evaluation of projects' 523 strengths, weaknesses and characteristics at key stages, in order to ensure acceptable 524 mitigation strategies are evolved for addressing emerging threats to project bankability.

525 This study therefore offers a relatable and simple schema for understanding bankability of 526 critical risks in PFI/PPP projects, particularly for less statistically inclined PPP practitioners

- 527 who require the much-needed private finance for facilitating important PPP infrastructure
- 528 projects.

529 **References**

- Akintoye, A., Hardcastle, C., Beck, M., Chinyio, E., and Asenova, D. (2003), Achieving Best
 Value in Private Finance Initiative Project Procurement. Construction Management
 and Economics. 21(5), 461-470.
- Al-Bahar, J. F. and Crandall, K. C. (1990), Systematic Risk Management Approach for
 Construction Projects. Journal of Construction Engineering and Management. 116(3),
 533-546.
- Ameyaw, E. E., & Chan, A. P. (2015). Evaluation and ranking of risk factors in public–
 private partnership water supply projects in developing countries using fuzzy
 synthetic evaluation approach. *Expert Systems with Applications*, 42(12), 5102 5116
- Bertram, P., Rösch, D., and Sibbertsen, P., (2012), "The benefits and limitations of risk models". Union Investment, Risk Management Edition 1.11.pp 1-12.
- Boateng, P., Chen, Z., & Ogunlana, S. O. (2015). An Analytical Network Process model for
 risks prioritisation in megaprojects. *International Journal of Project Management*,
 33(8), 1795-1811.
- 545 Burke, R., & Demirag, I. (2015). Changing perceptions on PPP games: Demand risk in Irish
 546 roads. *Critical Perspectives on Accounting*, 27, 189-208.
- 547 Carbonara, N., Costantino, N., Gunnigan, L., & Pellegrino, R. (2015). Risk Management in
 548 Motorway PPP Projects: Empirical-based Guidelines. Transport reviews, 35(2), 162549 182.
- Chan, A. P., Osei-Kyei, R., Hu, Y., & Yun, L. E. (2018). A fuzzy model for assessing the risk
 exposure of procuring infrastructure mega-projects through public-private partnership:
 The case of Hong Kong-Zhuhai-Macao Bridge. *Frontiers of Engineering Management*,
 5(1), 64-77.
- Delmon, J., (2011), Public–Private Partnership Projects in Infrastructure: An Essential
 Guide for Policy Makers. New York: Cambridge university press.
- Delmon, J. (2017). Public-private partnership projects in infrastructure: an essential guide
 for policy makers. Cambridge University Press.
- Demirag, I., Khadaroo, I., Stapleton, P., and Stevenson, C., (2011), Risks and the Financing
 of PPP: Perspectives from the Financiers. *The British Accounting Review*, 43 (2011)
 294–310.
- 561 Esty, B. C. (2004), Why study large projects? An Introduction to Research on Project Finance.
 562 [Online]. European Financial Management. 10(2), 213-224. [Accessed: 12th Oct, 2014].

- Finnerty, J. D. (2013), Project Financing: Asset-Based Financial Engineering. John Wiley &
 Sons.
- Grimsey, D., and Lewis, M., (2002), "Evaluating the Risks on Public Private Partnerships for
 Infrastructure Projects", *International Journal of Project Management*, Vol. 20, pp. 107 118.
- He, Q., Luo, L., Hu, Y., & Chan, A. P. (2015). Measuring the complexity of mega construction
 projects in China—A fuzzy analytic network process analysis. International Journal of
 Project Management, 33(3), 549-563.
- 571 HM Treasury, (1997), Partnerships for Prosperity. HM Treasury, London, November.
- 572 HM Treasury (2012), PFI Summary Data. [Online] Available at:
 573 https://www.gov.uk/.../summary_document_pfi_data_march_2012.pdf. [Accessed: 12th
 574 September, 2015).
- Hoffman, S.L., (2008), The Law and Business of International Project Finance. 3rd ed. New
 York: Cambridge University press.
- 577 Kumar, L., Jindal, A., & Velaga, N. R. (2018). Financial risk assessment and modelling of
 578 PPP based Indian highway infrastructure projects. *Transport Policy*, 62, 2-11.
- Lavasani, S. M., Ramzali, N., Sabzalipour, F., & Akyuz, E. (2015). Utilisation of fuzzy fault
 tree analysis (FFTA) for quantified risk analysis of leakage in abandoned oil and
 natural-gas wells. Ocean Engineering, 108, 729-737.
- Li, Z., Tian, Y., Li, K., Zhou, F., & Yang, W. (2017). Reject inference in credit scoring using
 Semi-supervised Support Vector Machines. Expert Systems with Applications, 74, 105 114.
- Liu, T., Wang, Y., & Wilkinson, S. (2016). Identifying critical factors affecting the
 effectiveness and efficiency of tendering processes in Public–Private Partnerships
 (PPPs): A comparative analysis of Australia and China. International Journal of Project
 Management, 34(4), 701-716.
- Loosemore, M., & Cheung, E. (2015). Implementing systems thinking to manage risk in
 public private partnership projects. International Journal of Project Management,
 33(6), 1325-1334.
- Meng, X. and McKevitt N., (2011), "Improving the Bankability of a PFI Financing
 Application". *The Journal of Structured Finance*, Vol.17 (3), pp. 78-87.
- Moody's Investors Service (2016). Rating Methodology for Construction Risk in Privately Finance Public Infrastructure (PFI/PPP/P3) Projects. Available Online
 [https://www.globalinfrafacility.org/sites/gif/files/Moody%27s-
- 597 Rating%20Methodology%20%20Construction%20Risk%20in%20PPP%20projects.pdf].
 598 Accessed on 20th June, 2019).
- 599 Oyedele, L., (2013), "Avoiding Performance Failure Payment Deductions in PFI/PPP Projects:
 600 Model of Critical Success Factors". Journal of Performance of Constructed Facilities.
 601 Volume 27, Issue 3 (June 2013), pp. 283–294.

- Osei-Kyei, R., & Chan, A. P. (2017). Implementing public–private partnership (PPP) policy
 for public construction projects in Ghana: critical success factors and policy
 implications. International Journal of Construction Management, 17(2), 113-123.
- Osei-Kyei, R., & Chan, A. P. (2015). Review of studies on the Critical Success Factors for
 Public–Private Partnership (PPP) projects from 1990 to 2013. International journal of
 project management, 33(6), 1335-1346.
- 608 Owolabi, H. A., Bilal, M., Oyedele, L. O., Alaka, H. A., Ajayi, S. O., & Akinade, O. O. (2018).
 609 Predicting completion risk in PPP projects using big data analytics. *IEEE* 610 *Transactions on Engineering Management*.
- Özdemir, E. (2015). Experience in structuring public-private partnerships for airports.
 Journal of Airport Management, 9(2), 154-161.
- Pantelias, A., & Roumboutsos, A. (2015). A conceptual framework for transport
 infrastructure PPP project credit assessments. Journal of Finance and Economics, 3(6),
 105-111.
- 616 Perold, A., (2004), "Capital Asset Pricing Model". *Journal of Economic Perspectives*—Volume
 617 18, Number 3.pp 3-24.
- Regan, M., Smith, J., & Love, P. E. (2017). Financing of public private partnerships:
 Transactional evidence from Australian toll roads. *Case studies on transport policy*, 5(2), 267-278.
- Smith, N. J., Merna, T., & Jobling, P. (2014). Managing risk in construction projects. John
 Wiley & Sons.
- Valipour, A., Yahaya, N., Md Noor, N., Mardani, A., & Antuchevičienė, J. (2016). A new
 hybrid fuzzy cybernetic analytic network process model to identify shared risks in PPP
 projects. International Journal of Strategic Property Management, 20(4), 409-426.
- Wibowo, A., & Alfen, H. W. (2015). Government-led critical success factors in PPP
 infrastructure development. Built Environment Project and Asset Management, 5(1),
 121-134.
- Ku, Y., Chan, A. P., Xia, B., Qian, Q. K., Liu, Y., & Peng, Y. (2015). Critical risk factors
 affecting the implementation of PPP waste-to-energy projects in China. Applied energy,
 158, 403-411.
- Yilmaz, K. (2013). Comparison of quantitative and qualitative research traditions:
 Epistemological, theoretical, and methodological differences. *European Journal of Education*, 48(2), 311-325.
- 635 Yin, R. K. (2017). Case study research and applications: Design and methods. Sage636 publications.
- 637 Yescombe, E. R. (2013), Principles of Project Finance. Academic Press.
- K. (2004), Improving Concessionaire Selection Protocols in Public/Private Partnered
 Infrastructure Projects. Journal of Construction Engineering and Management, 130(5),
 670-679.

pg. 22

- 641 Zhu, L., & Chua, D. K. H. (2018). Identifying Critical Bankability Criteria for PPP Projects:
 642 The Case of China. Advances in Civil Engineering, 2018.
- 643 Zou, P. X., Wang, S., & Fang, D. (2008). A life-cycle risk management framework for PPP
 644 infrastructure projects. Journal of financial management of property and construction,
 645 13(2), 123-142.
- 646

<u>List of Tables</u>

Table 1: Existing lenders' assessment criteria/techniques for PPP projects and their shortcomings

S/N	Source & Year	Primary Aim/s	Methodology	Shortcomings
1	Basel I (1988) also known as Basel Accord	Focus is on minimum capital requirements (capital adequacy) that banks & other international lenders must hold to mitigate default risk (credit risk).	Credit Risk analysis using Risk Weighted Average (RWA). Banks to hold capital/assets (i.e. Tier 1, Tier 2 and Tier 3 assets) equal to 8% of RWA. Total Capital ratio = Capital/Asset Value – All Risk Weight Average.	Basel-I provided no rule that considers the quality of the Counterparty (i.e. credit worthiness of big organisations i.e. a big company like IBM, Google, GE, Apple). Only focused on credit risk of the customer. Counterparty credit worthiness is essential for determining sponsors' risk in PPP as part of overall risk evaluation
2	Basel II (introduced in 1992)	 Requires banks to earmark sufficient capital to mitigate credit risk, market risk and operational risk. Emphasizes banks risk management practices (measurement) & Internal Capital Adequacy Assessment Process (ICAAP), (3) Regulatory reporting of bank's risk practices & (3). Market discipline via disclosure requirements. 	Retains capital adequacy requirement at 8% of RWA. Segmented some risk-free asset class into to Govt. bank & corporate bonds at (0%,20% & 20%) respectively. Provided framework for managing residual risks in assets or investments.	(1) Internal risk models of banks performed poorly and understated risk exposure and could mislead investors as well. (2) Many PPP Contractors (especially less financially savvy construction & engineering contractors) lack the high-level of technical understanding of risk quantification & modelling. (3) Complex nature of BASEL regulations makes it hard for ordinary PPP practitioners & contractors to connect with.

3	Basel III (2010 - 2013)	 Strengthens bank's capital adequacy by increasing liquidity & reducing bank's leverage: Introduced a non-risk-based measure for minimum capital requirements Introduced minimum leverage ratio (liquidity cover ratio (LRC) & net stable funding ratio (NSFR) Introduced capital requirements for counterparty credit risk using Credit Value Adjustment (CVA) etc. 	 Retains RWA at 8%. Increase of 2.5% capital conservation buffer bringing common equity requirements of banks to 7.5%. Banks to now hold 10.5% of risk-weighted assets. Leverage ratio fixed at 3% of banks' tier 1 capital/banks' av. total consolidated assets etc. 	(1) Complex nature of BASEL III regulations makes it hard for ordinary PPP practitioners & contractors to easily connect with and created over-reliance financial experts' consultants during PPP structuring & development, which is costly and overall contributes to higher project cost.
4	Carbonara et al. (2015)	(1) Provided guidelines for public & private parties for identifying significant risks in PPPs including suitable mitigation strategies. (2) Focused on risks associated with PPP development phase, construction, O&M and transfer phases including life cycle risks.	Mixed method by combining delphi survey with multiple case studies	(1) Study focused only on risk & mitigation strategies without revealing bankability criteria which project financiers will be interested in before approving loan. (2) Availability of mitigation strategies for risks does not necessarily guarantee bank funding approval, since many other situational factors can swing lenders' decision.
5	Moody's (2016)	 Presents rating methodology for construction Risk in privately-financed public infrastructure. Explains Moody's approach to assessing credit risk in PFI/PPP/P3 projects in construction globally. 	(1) Focuses on projects where Government pays either at the completion of key milestones or via unitary payments. (2) Methodology uses a Grid approach and developed a 5-Grid factor for assessing and weighing credit risk in construction PPP (i.e. Construction risk allocation between public & private parties, project complexity, consortium experience & project readiness, resilience of constructor to cost overrun, resilience of project to schedule overrun).	(1) This methodology does not account for projects financed purely on commercial terms, as it leans more towards government-backed projects (sovereign credit rating) due to the guarantee of more stable streams of income. Hence, projects with no such terms requires more information than has been put forward in Moody's rating methodology. (2) The methodology agreed it had not been exhaustive of all factors considered by internal evaluators, indicating insufficient information for contractors to rely on. This also plays into the criticism of secrecy in PPP lending arrangements that dominates the literature.

6	Pantelias &	(1) Investigated credit worthiness assessment of	Proposed a framework for evaluating credit risk in	The study lumps together credit risk evaluation with other risk analysis
	Roumboutsos,	transport infrastructure PPP projects.	transport PPP projects involving considerations for	in PPP. The study treated credit risk/default risk more or less like the
	(2015)	(2) Examines credit risk analysis and methodology of	contractual agreements describing the risks	source of other risks in PPP, which is not the case. Although, credit
		credit rating agencies (CRA).	considered, the individual assessment of each risk	risk is only the 1st risk evaluation conducted by lenders, however, credit
		(3) challenged over-emphasis placed on construction	and their allocation. The framework is based on	worthiness of projects can change during the project life cycle due to
		phase of PPPs including omission of key transport	generic classification of risk encountered in PPP	the emergent of other critical risks.
		sector contextual factors necessary for credit analysis.	lifecycle. Suggested the need for project credit risk.	
7	Credit Rating	Step-by-step Analysis of project credit worthiness	Sensitivity analysis, risk modelling & qualitative	There is an observed bias of placing disproportionate emphasis on risks
	Agencies (i.e. S&P,	including financial analysis and sensitivity. Combines	appraisals.	at construction phase as against other phases in the project life cycle
	Fitch, Moody's)	qualitative and quantitative risk modelling & analysis.		(Pantelias & Roumboutsos, 2015). Most evaluations leverage sovereign
				credit ratings to the exclusion of projects not enjoying such.
8	Statistical & analytic	Leverages statistical inferences to derive suitable	Build quantitative models i.e. Monte-Carlo, Fuzzy	Many PPP Contractors (especially less financially savvy construction &
	Models	relationship for decision making	Models etc. to simulate project risk	engineering contractors) lack the high-level financial engineering
				knowledge involved with such statistical modelling. Asides big
				contractors who are able to pay for hiring internal or independent
				financial experts, SME contractors hoping to penetrate PPP market
				will cannot afford the cost involved in such pre-contract due diligence

				Case Study for Model				Case Study For				
Risk Factors	Risk Mitigation Strategies Proffered by Project	Lenders Bankability Criteria for Project	Development			• •	Model Validation					
(RF)	Sponsors	Appraisal	Road	Sector	Education	Sector	Road	Sector	Education Sector			
. ,			Case	Case	Case	Case	Case	Case	Case	Case		
			study	study	Study	Study	Study	Study	Study	Study		
	Supply price hedging	Existence of fair hedge contract on supplies of	20*	25*	22*	18	27*	20*	21*	23*		
RF.1		Supply contract with a reliable and experienced										
	Long-term supply contract with reliable suppliers	input supplier	25*	15	20*	25*	20*	31*	20*	21*		
Supply Risk	Accurate estimate of bill of quantity	Accurate estimate of bill of quantity for supplies	8	6	7	9	4	14	8	11		
	Supply contract with only one supplier	Existence of multiple raw material suppliers	10	5	20	5	10	23	10	12		
	None existences of supply default penalty	Non-Supply Penalty to supplier	32*	35*	28*	19	30*	33*	29*	35*		
	Long term offtake/traffic/revenue contract	Long term purchase contractual arrangement	5	5	15	17	15	20	5	6		
		with reliable purchaser										
RF2	Predictably robust project cash flows	Predictably robust project cash flows	40*	40*	38*	40*	45*	41*	40*	37*		
Demand	Accurate revenue/market forecast and analysis	Traffic/revenue forecast from an independent	15	30*	10	13	32*	36*	25*	22*		
	Existence of Shadow toll contractual	Existence of Shadow toll contract arrangement	5	27*			50*	A5*		_		
Risk	arrangement	Existence of shadow ton contract an angement	5	37	_		50	45		_		
	Not provided	Existence of Pass-Through Contract	6	7	7	5	9	4	9	7		
	Not provided	Government Guarantee of cash flow shortfall.	50*	38*	5	5	45*	35*	15	11		
	Long-term Operations and Maintenance (O&M)	Long-term Operations & Maintenance (O&M)	30*	25*	20*	28*	30*	34*	30*	27*		
	contract	contract										

Table 2: Rule-Based Model Scores for Lenders' Bankability Criteria Employed in the Case Study Projects

			Case Study for Model				Case Study For					
	Risk Mitigation Strategies Proffered by Project	Landers Darkskility Oritaria for Drainst	Development					Model V	alidation			
Risk Factors		Lenders Bankability Criteria for Project	Road	Sector	Education Sector		Road Sector		Education Secto			
(RF)	Sponsors	Appraisai	Proi	ects	Proiec	ts	Pro	iects	Proiects			
			Case study	Case study	Case Study	Case Study	Case Study	Case Study	Case Study	Case Study		
	O&M contractor with competence and robust	O&M contractor's competence and financial	20*	20*	25*	21*	20*	22*	25*	27*		
	financial status	strength	20	20	33		20	25	23	27		
	Financial strength of project SPV towards project	Experienced and skilled operation and	23*	20*	20*	15	20*	17	15	19		
	maintenance	Maintenance staff within the SPV										
	Existence of Lender right to remove O&M	Existence of Lender right to remove O&M	22*	25*	22*	18	20*	20*	20*	24		
	operator and revoke contract due to	operator and revoke contract due to		2.5		10	20	20	20	24		
	Existence liquidated damages and penalties	Deufermenes Deced Contract	20*	21*	10	22*	21*	20*	20*	20*		
RF.3	contract (Performance Failure Deductions etc.)	Performance based Contract.	201	21.	10	25	21	30	30	201		
	Incentives to O&M Operator for maintaining	Incentives to O&M Operator for maintaining high	10	12	6	8	7	9	7	7		
	high efficiency levels	efficiency levels						Ē				
Operation &	Net see de d	O&M operator's familiarity with the project	20*	 *)) * 15	20*	10	15	10	17		
Maintenance	Not provided	technology being used	201	25	15	201		15	10	12		
Risk	Net provided	O&M Operator's Guarantee from Parent	0		0	7	0	F	F	0		
		Company	9	5	0		9	5	5	9		
	Not provided	Existence of experienced and independent O&M	6	8	5	7	7	6	4	5		
		contractor rather than self-maintenance by SPV			-							
	Not provided	Sponsor to maintain a "Maintenance Reserve	4	9	8	5	7	4	7	7		
		Account"										
	Robust cover ratios (Annual Debt Service Cover	Robust cover ratios (Annual Debt Service Cover	50*	25*	35* 40*	42*	44*	10*	л 2 *	18*		
	Ratio and Loan Life Cover Ratio).	Ratio and Loan Life Cover Ratio).	50*	50° 35*				42*	43	40		

pg. 28

			Case Study for Model				Case Study For				
	Disk Mitigation Strategies Droffered by Dreiset	Londors Bankability Critoria for Project	Development					Model V	alidation		
Risk Factors	Risk Mitigation Strategies Proffered by Project		Road Sector		Education Sector		Road Sector		Education Sector		
(RF)	Sponsors	Appraisai	Pro	iects	Proiec	ts	Proiects		Proiects		
			Case study	Case study	Case Study	Case Study	Case Study	Case Study	Case Study	Case Study	
		Construction contractor with years of experience		- child	ciacy				- child		
	Construction contractor's competence	of successful completion of project finance	35*	32*	30*	35*	25*	27*	35*	30*	
	Construction contractor with strong financial	Construction contractor with financial strength.	30*	25*	25*	19	21*	35*	31*	26*	
	standing										
	Evistance of an Indonendant technical event	Sponsor to engage Independent Technical	20*	21*	20*	20*	7 2*	24*	27*	24*	
		Consultant (ITC)	20	20 31	201	20	23	54	27		
	Tried-and Tested Technology for the	Tried-and Tested technology for the construction	20*	20*	15	10	21*	21*	20*	10	
	construction of project delivery.	of project.	20	20	15	10	21	24	20	15	
	Contract on pre-estimated liquidated damages	Not Considered	7	5	4	6	11	5	8	11	
	for project deficiencies										
	Periodic construction mile stone reports	Not Considered	5	4	8	9	13	6	6	8	
	Short Notice, close supervision and monitoring	Not Considered	4	a	o	7	7	7	5	6	
	of Construction works.			3	5 5	ŕ		,	J	6	
	Contractor's liability insurance cover	Construction contractor with a liability insurance	15	20*	21*	27*	20*	25*	20*	25*	
	contractor's all risk	cover.	15	20	51	27	50	25	25	25	
	Pre-completion guarantee or full financial	Pre- completion guarantee or full financial	24*	0.5 *	20*	 *	20*		20*	45	
	guarantee from the Sponsor to the lender.	guarantee from the sponsor at construction	21*	21* 25*	30*	28*	20*	21*	20*	15	
	Eived Drice Turn Koy (EDTK) contract	Eived Drice Turn Koy (EDTK) contract	20*	20*	25*	20*	26*	20*	20*	27*	
	Fixed Price Turn Key (FPTK) contract	Fixed Frice Turn Key (FPTK) contract.	30*	28*	35*	30*	20*	38 [~]	29*	3Z**	
	Not provided	Contractor's acceptance of Full Technology Wrap	7	6	4	6	10	11	7	7	
		for the proper functioning of all project assets		-		-					
	Not provided	Delay in start-up insurance	20*	20*	21*	26*	21*	23*	15	21*	

		Lenders Bankability Criteria for Project Appraisal		Case Study for Model			Case Study For Model Validation				
Risk Factors (RF)	Risk Mitigation Strategies Proffered by Project Sponsors			Road Sector Proiects Case Case study study		Sector ts Case Study	Road Sector Proiects Case Case Study Study		Education Se Projects Case Ca Study Stu		
RF.4	Not provided	Single -Point responsibility from main contractor to be responsible for other subcontractors.	2	9	5	9	9	10	8	5	
Construction	Not provided	Contractor bonding through Bank Guarantee	3	5	4	7	11	7	9	11	
	Not provided	Additional equity requirements from the sponsors in case of cost over run	5	8	8	4	8	8	6	8	
&Completion	Not provided	Debt Buy Out arrangement	6	7	6	3	10	5	11	7	
Risk	Not provided	Acceptance by the contractor of responsibility for every aspect of construction and design	8	5	9	7	7	4	9	6	
		Total Scores	668	705	633	611	755	797	653	659	
		Lenders' Minimum Bankability	600	600	525	550	650	700	550	520	

Major Risk Factor	Concurrent Risks emerging	Types of projects where they are common
Supply Risk	Volume Risk Price Risk Reserve Risk	Most Gas propelled power plants Oil field explorations Infrastructures Waste management facilities
Demand Risk	Price Risk Volume Risk	Road Concessions Power Projects Air ports Oil and Gas Rail Concessions etc.
Operations and Maintenance Risk	Performance Risk Availability Risk	Common to most project finance contracts
Construction/Completion Risk	Technology Risk Cost Overrun Time Overrun	Common to most project finance contracts

Table 3: Risks and other Emerging Sub-Risk Components in PFI/PPP Projects.

Notes: Qualitative evidences showed that, the existence of certain critical risks automatically results in other smaller chain of sub-risk components in PFI projects. This explained the need for project stakeholders to be well equipped and be able to anticipate such concurrent relationships among risks during due diligence appraisals.

Table 4: Framework Validation using Four PPP Case Studies

A brief description of PPP projects' case studies used for validating the framework model focused on essential features of each of the project.

Four Case Studies for Model Validation									
Case Study A (Road Project)	Case Study B (Road Project)	Case study C (School Project)	Case Study D (School Project)						
The project, located in Wales, is a 32km dual carriage way designed, built, finance and operate under a 30-year concession agreement. Awarded under PFI/PPP scheme in 1998, the project is valued at £125million and involved maintenance of additional 12km existing road and two bridges. As part of the concession contract, the project company was also responsible for ecological and landscape design of the road. The road project was completed within 24months and started operations in the early part of year 2002 under a shadow-toll arrangement.	This project is one of the early set of Design, Build, Finance and Operate (DBFO) road projects in the UK and is located in South West of England. Valued at £125million, the 33-year concession involved the upgrade of two major link roads of approximately 52km, to dual carriageway status. Concessioned in the late 1990s, the project also involved improvement and maintenance of three additional trunk roads of 6km, 10km, and 9km respectively. The construction phase of the project was completed within 20months and the project had since commenced operations towards the end of year 2000.	This project is part of the "Building School for the Future" (BSF) project of the UK government and is located in the North East of England. With a project value of £55million, the project was concessioned to private sector under a 25-year contract that involved a combination of build, remodel/refurbish of 6 secondary schools. The PFI project also included facility maintenance services up to the tune of £20million for three of the PFI schools. Awarded as a DBFO in 2009, the construction of the project took 17months and had since being in operation as at year 2013.	This project involved the Design, Construction, Finance and Operation of four new secondary schools in the South West of England. The project value was put at £119m and was contracted under a 25-year concession. The schools were designed to accommodate 945 pupils of 11 to 16 years of age. As part of the PFI arrangement, the private sector contractor was responsible for refurbishment and maintenance of the facilities, while also providing ICT, catering, security, fitness centre, dance studio and all weather pitches with floodlights etc. The project was delivered within 24months and is currently up and running.						