

## THE EVOLUTIONARY SEQUENCE OF ACTIVE GALACTIC NUCLEI AND GALAXY FORMATION REVEALED

M. J. PAGE

Mullard Space Science Laboratory, University College London, Holmbury St. Mary, Dorking, Surrey RH5 6NT, UK; mjp@mssl.ucl.ac.uk

J. A. STEVENS AND R. J. IVISON

Astronomy Technology Center, Royal Observatory, Blackford Hill, Edinburgh EH9 3HJ, UK; jas@roe.ac.uk, rji@roe.ac.uk

AND

F. J. CARRERA

Instituto de Física de Cantabria, CSIC, Universidad de Cantabria, 39005 Santander, Spain; carrera@ifca.unican.es

Received 2004 April 27; accepted 2004 July 2; published 2004 July 21

### ABSTRACT

Today, almost every galaxy spheroid contains a massive black hole: a remnant of, and testament to, a period in its evolution when it contained an active galactic nucleus (AGN). However, the sequence and timescales of the formation of the black hole and surrounding spheroid of stars are completely unknown, leaving a large gap in our knowledge of how the universe attained its present appearance. Here we present submillimeter observations of matched samples of X-ray absorbed and unabsorbed AGNs that have luminosities and redshifts characteristic of the sources responsible for most of the mass in present-day black holes. Strong submillimeter emission, an isotropic signature of copious star formation, is found only in the X-ray-absorbed sample, ruling out orientation effects as the cause of the absorption. The space density and luminosity range of the X-ray-absorbed AGNs indicate that they are undergoing the transition between a hidden growth phase and an unabsorbed AGN phase and imply that the X-ray-absorbed period in the AGN's evolution coincides with the formation of the galaxy spheroid.

*Subject headings:* galaxies: active — galaxies: evolution — galaxies: formation

### 1. INTRODUCTION

It is now known that the histories of cosmic star formation and luminous active galactic nucleus (AGN) activity track each other rather well, both showing a dramatic decline between  $z \sim 2$  and the present day (Franceschini et al. 1999). Their legacy, the prevalence of massive black holes today (Yu & Tremaine 2002) and the proportionality between black hole mass and the mass of their host galaxy spheroids (Merritt & Ferrarese 2001), is most easily explained if the formation of the two components was coeval, i.e., the black hole was built up by accretion of the same gas that rapidly formed the stars of the spheroid. During this formation episode, the average bolometric luminosity of the stellar component is expected to exceed that emitted by the AGN by a factor of a few (Page et al. 2001a). Under such circumstances, a large fraction of stellar mass must have built up around the AGNs that dominate the accretion power of the universe, because these were responsible for the majority of present-day black hole mass. The bulk of the comoving luminosity density was produced by objects with luminosities close to the break luminosity  $L_*$ , on account of the AGN luminosity function at any redshift being characterized by a broken power law (Page et al. 1997; Boyle et al. 2000). While the X-ray background is chiefly produced by AGNs at  $z < 2$  (e.g., Barger et al. 2001), the luminosity density of AGNs was at its peak between  $z = 1$  and 3 (Page et al. 1997; Miyaji et al. 2001). Therefore, coeval black hole/stellar bulge formation would imply that a large fraction of the universe's star formation took place around AGNs with  $1 < z < 3$ , and  $\log L = \log L_* \pm 0.7$ .

Submillimeter observations have already shown that there is a significant overlap between the bulge and black hole growth phases in X-ray-absorbed QSOs in this range of redshifts and luminosities (Page et al. 2001a). These enigmatic objects are characterized by significant X-ray absorption (column densities of  $21.4 < \log N_{\text{H}} < 22.5$ ) but little or no obscuration to their

broad emission lines and ultraviolet continua (Page et al. 2001b). However, sensitive submillimeter observations have been performed for only eight such objects, and hence the temporal overlap between black hole and bulge growth phases is subject to considerable statistical uncertainty. More importantly, there were no sensitive submillimeter observations of a comparable sample of unabsorbed QSOs, which represent the majority of QSOs selected in soft X-ray surveys. Therefore we followed up this initial result with an experiment involving a larger sample of 20 unabsorbed objects. This sample is matched in luminosity and redshift to the original sample; it encompasses all of the crucial  $1 < z < 3$ ,  $\log L = \log L_* \pm 0.7$  region that can be viably investigated with the Submillimeter Common-User Bolometer Array (SCUBA) at the James Clerk Maxwell Telescope (JCMT). Figure 1 shows the region of redshift-luminosity space from which the sample is drawn. The sample was drawn from a combination of several surveys: the Extended *Einstein* Medium Sensitivity Survey (Stocke et al. 1991), the *R OSAT* International X-Ray Optical Survey (Mason et al. 2000), the UK *ROSAT* Deep Survey (McHardy et al. 1998), the Cambridge–Cambridge *ROSAT* Serendipity Survey (Boyle et al. 1997), the QSF 1 and QSF 3 fields (Griffiths et al. 1995), and the Lockman Hole (Schmidt et al. 1998). The wide range of flux limits covered by these surveys is crucial in providing AGNs over the required range of redshift-luminosity space. In all practical respects this sample is comparable to the original sample, except that it is composed of AGNs that are unabsorbed in the X-ray band. A Hubble constant  $H_0 = 70$  km s<sup>-1</sup> Mpc<sup>-1</sup> and density parameters  $\Omega_{\Lambda} = 0.7$  and  $\Omega_m = 0.3$  are assumed throughout this Letter.

### 2. OBSERVATIONS AND DATA REDUCTION

Observations at 850  $\mu\text{m}$  were carried out at the JCMT between 2002 December and 2003 March. The observations were carried out in photometry mode, in which the source is placed




FIG. 1.—Selection of the sample. The data points show the redshifts and X-ray luminosities of X-ray–selected AGNs from a number of surveys with different flux limits and sky areas. The thin solid line shows the position of  $\log L_*$  as a function of redshift assuming the best-fit model luminosity function from Page et al. (1997), and the thick solid line encloses the region ( $1 < z < 3$ ,  $\log L_* - 0.7 < \log L < \log L_* + 0.7$ ), in which the majority of AGN comoving luminosity density is produced. The bold dashed line is the limit at which sources are expected to have a flux of 3 mJy at 850  $\mu\text{m}$  if they have star formation–powered far-infrared (FIR) luminosities equal to their AGN bolometric luminosities, and assuming FIR spectra similar to that of Mrk 231. The AGNs above the dashed line but within the region enclosed by the thick line are the objects that can be usefully probed with SCUBA and are relevant to the production of the universe’s accretion luminosity. Sources selected for submillimeter observations are shown in black rather than gray.

on the central bolometer of the array and the secondary mirror is jiggled in a  $3 \times 3$  pattern with  $2''$  intervals with a 1 s integration at each position. The secondary mirror was chopped  $45''$  in azimuth at a frequency of 7.8 Hz and nodded between the source and reference positions every 18 s. Data were reduced using the standard STARLINK SURF software. After compensating for the nod, the data were flat-fielded and corrected for atmospheric extinction. Each jiggle in turn was then corrected for residual sky noise, which is correlated across the SCUBA field of view and often dominates the signal from faint sources. These sky offsets were taken to be the median signal from all bolometers on the given array (excluding noisy bolometers).

### 3. RESULTS AND DISCUSSION

The measured 850  $\mu\text{m}$  flux densities for the X-ray–unabsorbed QSOs are given in Table 1. Only one source (RX J141954) is detected with  $3 \sigma$  confidence, and none of the sources is brighter than the  $5 \sigma/5$  mJy level. This lack of detections is in stark contrast to the sample of X-ray–absorbed QSOs observed in 2001, of which 50% are brighter than 5 mJy (Fig. 2). Far from

TABLE 1  
CHARACTERISTICS OF THE UNABSORBED SAMPLE AND THEIR  
OBSERVED SUBMILLIMETER EMISSION

Source	$z$	$\log L_x$	$S_{850}$
RX J105316.8+573552 .....	1.204	44.9	$-0.3 \pm 0.9$
MS 0537.4–2843 .....	1.245	44.9	$1.5 \pm 0.9$
RX J125456.9+564941 .....	1.261	44.9	$1.6 \pm 1.0$
RX J125639.5+472410 .....	1.315	45.0	$0.9 \pm 1.0$
MS 1633.1+2643 .....	1.336	44.9	$-0.4 \pm 0.8$
MS 1703.5+6052 .....	1.358	44.9	$0.0 \pm 1.0$
RX J071858.8+712432 .....	1.390	44.9	$1.7 \pm 0.9$
MS 0824.2+0327 .....	1.431	44.9	$-1.3 \pm 0.9$
RX J100926.3+533424 .....	1.718	45.0	$-0.2 \pm 1.0$
RX J105649.6+493412 .....	1.788	45.1	$0.9 \pm 1.1$
RX J111918.6+211339 .....	1.818	44.9	$-0.2 \pm 1.2$
RX J180534.0+694733 .....	1.820	45.0	$-1.0 \pm 1.0$
RX J104718.6+541919 .....	1.823	44.9	$0.2 \pm 1.0$
RX J232443.6+231537 .....	1.840	45.0	$1.3 \pm 0.9$
RX J113655.3+295131 .....	1.861	44.9	$0.5 \pm 0.9$
RX J112106.0+133825 .....	1.940	45.1	$1.8 \pm 0.9$
RX J105331.8+572454 .....	1.956	45.0	$1.9 \pm 0.8$
CRSS J1428.3+4231 .....	2.171	45.1	$0.6 \pm 1.0$
RX J141954.3+543014 <sup>a</sup> .....	2.248	45.1	$2.8 \pm 0.8$
CRSS J1415.1+1140 .....	2.353	45.0	$0.2 \pm 0.9$

NOTES.— $L_x$  is the 0.5–2 keV X-ray luminosity in units of  $\text{ergs s}^{-1}$ ;  $S_{850}$  is the 850  $\mu\text{m}$  flux density in units of millijanskys.

<sup>a</sup> Source detected at  $3 \sigma$  confidence at 850  $\mu\text{m}$ .

simply improving the statistical uncertainty inherent to our original sample, the results for the unabsorbed AGNs are incompatible with those for the absorbed sample. The lack of 5 mJy detections in the unabsorbed sample implies that at 95% confidence less than 14% of unabsorbed QSOs are bright submillimeter sources (Gehrels 1986), whereas the detection rate of the X-ray–absorbed sources implies that at least 19% of X-ray–absorbed QSOs are bright submillimeter sources.

Our observations imply that unabsorbed QSOs, which have been studied for 30 years and of which we know tens of thousands of examples, do not play a significant role in the universe’s star formation history. In contrast, the X-ray–absorbed QSOs at  $z > 1.5$  are embedded in the massive starbursts of still-forming galaxy spheroids.

To see why this is such a surprising and consequential result, we must consider the alternative models for the X-ray absorption in QSOs. By far the most widespread and most paradigmatic model is the AGN “unified scheme” (Antonucci 1993) in which the absorbing material is present in all objects in the form of a toroidal structure. In this model, absorbed and unabsorbed AGNs are intrinsically identical, with the torus producing absorption in those objects viewed through it. This model is well established for the nearby lower luminosity Seyfert galaxies, although there are some notable discrepancies (e.g., Tran 2003 and references therein) and most X-ray background synthesis and AGN population models are predicated on this concept (Setti & Woltjer 1989; Comastri et al. 1995; Gilli et al. 2001). The more speculative alternative is that X-ray absorbed and unabsorbed QSOs are intrinsically different objects. In particular, it has been proposed that substantial absorption could be a defining characteristic of the early phases of QSO evolution (Fabian 1999). In such models, the main obscured growth phase of the QSO coincides with the formation of the host galaxy spheroid, the completion of which coincides with the luminous unobscured phase of the QSO’s evolution (Silk & Rees 1998; Sanders et al. 1988). In the unified scheme, any submillimeter emission powered by the nucleus will be orientation independent because the obscuring torus is optically thin at submillimeter wavelengths. Submillimeter emission orig-




FIG. 2.—*Left*:  $850\ \mu\text{m}$  flux densities of the sample of 20 X-ray-unabsorbed QSOs. *Right*:  $850\ \mu\text{m}$  flux densities of the matched sample of X-ray-absorbed QSOs, adapted from Page et al. (2001a). In both panels, sources that are detected at greater than  $3\ \sigma$  confidence are plotted as filled circles, while nondetections are shown as open circles. The solid line on both panels shows the predicted  $850\ \mu\text{m}$  flux density of the nearby submillimeter luminous, X-ray-absorbed QSO Mrk 231 if it were viewed at redshift  $z$ .

inating in star-forming regions will be similarly isotropic. Thus, if the X-ray-absorbed QSOs are absorbed because of their orientation to our line of sight, their submillimeter properties will be indistinguishable from those of X-ray-unabsorbed QSOs.

Immediately then, the level of segregation that we have found in the submillimeter properties of the X-ray absorbed and unabsorbed sources allows us to rule out orientation as the cause of the X-ray absorption. It therefore seems likely that the absorbed and unabsorbed QSOs represent different stages in an evolutionary sequence, in which the absorbed QSOs represent the earlier phase. This hypothesis is confirmed by *Hubble Space Telescope* images that show that the majority of unabsorbed QSOs lie in massive elliptical galaxies, at least for  $0 < z < 1$  (Kukula et al. 2001; Dunlop et al. 2003); their regular relaxed morphologies imply that these are essentially mature finished galaxies. Direct measurements of the morphologies and stellar masses of the host galaxies of unabsorbed QSOs at  $z > 1$ , while extremely difficult at present (e.g., Kukula et al. 2001; Croom et al. 2004), are also consistent with regular relaxed morphologies. The lack of submillimeter emission from our sample of  $1 < z < 3$  unabsorbed QSOs suggests that these objects also reside in relatively quiescent, fully formed host galaxies. Therefore, unabsorbed QSOs have already undergone a period of prodigious star formation in which they would have shone as powerful submillimeter sources. That the X-ray-absorbed QSOs are characterized by high submillimeter luminosities implies that they are embedded in the dense interstellar media of their forming host spheroids and therefore that they are still at this earlier evolutionary stage. Furthermore, the first submillimeter images of their megaparsec-scale environments indicate that they are located within significant overdensities of ultraluminous starburst galaxies that will rapidly evolve into rich clusters of galaxies typical of those that host X-ray-unabsorbed QSOs (Stevens et al. 2004).

We now argue that there is a particular time in the evolution of a typical QSO corresponding to the X-ray-absorbed phase. It immediately precedes the unabsorbed phase and lasts for only  $\sim 15\%$  of the lifetime of the optical QSO. First, their space density compared to unabsorbed QSOs allows us to make a crude estimate of the relative durations of the two phases. At a  $0.5\text{--}2\ \text{keV}$  flux of  $10^{-14}\ \text{ergs s}^{-1}\ \text{cm}^{-2}$ , the surface density of X-ray sources with

*ROSAT* spectra similar to the absorbed QSOs is  $19\ \text{deg}^{-2}$ , of which around half are broad-line objects (Page et al. 2000, 2001b). The fluxes must be corrected for absorption to allow a meaningful comparison with unabsorbed QSOs; the average flux correction factor for the QSOs from the hard-spectrum *ROSAT* survey is 1.5 (Page et al. 2001b). Thus there are about nine X-ray-absorbed QSOs per square degree with an absorption-corrected  $0.5\text{--}2\ \text{keV}$  flux of  $\geq 1.5 \times 10^{-14}\ \text{ergs s}^{-1}\ \text{cm}^{-2}$ . This flux limit corresponds to  $L_{0.5-2} = 4 \times 10^{44}\ \text{ergs s}^{-1}$  at  $z = 2$ , i.e., close to  $L_x$  in the epoch when QSO activity peaked (Page et al. 1997). For comparison, there are 60–70 unabsorbed QSOs at the same X-ray flux limit (Page et al. 1997; Miyaji et al. 2001). Assuming that absorbed and unabsorbed QSOs accrete with the same Eddington ratio, this implies that the X-ray-absorbed QSO phase typically lasts only around 15% as long as the unabsorbed phase (even less if QSOs accrete with higher Eddington ratios while they are still absorbed). Second, assuming that they accrete at 10% efficiency, that they do not exceed the Eddington limit, and that 3% of the accretion power is emitted in the  $0.5\text{--}2.0\ \text{keV}$  band (Elvis et al. 1994), their X-ray luminosities imply that they contain black holes of greater than  $10^8 M_\odot$ . Thus they are already relatively mature objects and cannot grow by accretion much further without producing black holes that are larger than those found in typical unabsorbed QSOs. However, since their host spheroids are still forming, this brief phase must precede the unabsorbed QSO with its complete quiescent spheroid. This strongly suggests that the X-ray-absorbed QSOs are observed during a transitional phase that immediately precedes the unabsorbed QSO, perhaps when the AGN has become powerful enough to eject the remaining cold interstellar medium and thereby terminate the growth of the spheroid (Fabian 1999; Silk & Rees 1998).

Before the X-ray-absorbed phase, there is an initial phase that is so highly obscured as to have been missed in all but the deepest X-ray surveys undertaken so far. This earliest phase corresponds to the main growth period of the host galaxy spheroid and so should be luminous in the submillimeter. During this phase the black hole must be accreting rapidly to achieve a mass of  $10^8 M_\odot$  and so must reach X-ray luminosities in excess of  $10^{44}\ \text{ergs s}^{-1}$ . If AGNs in this initial phase were not X-ray absorbed, then a significant fraction of unabsorbed QSOs would be luminous sub-

millimeter sources, but this is ruled out by our observations. If they were absorbed to a similar degree as the X-ray-absorbed QSOs, they would outnumber this population substantially at the flux limits probed by the hard-spectrum *ROSAT* survey and certainly would be found in large numbers just below this flux limit in the deeper surveys that are now being carried out with *XMM-Newton* and *Chandra*. This is not the case (Mainieri et al. 2002; Page et al. 2003), and hence the earlier evolutionary phases must be characterized by considerably higher levels of X-ray absorption ( $N_{\text{H}} > 10^{23} \text{ cm}^{-2}$ ). Since the great majority of optically selected QSOs show little or no X-ray absorption (Yuan et al. 1998), the earlier phases must also be heavily obscured in the rest-frame optical/UV. Consequently, AGNs in the earliest stages of their evolution will be difficult to detect in any wave band, except for the FIR/submillimeter where they will be strong sources. At present, the small number of optically faint, hard X-ray-detected submillimeter sources reported by Ivison et al. (2002) and Alexander et al. (2003) are probably the best candidates

for AGNs in this initial phase because they are more heavily obscured than our *ROSAT*-selected objects, although we can anticipate that future high-throughput X-ray observatories could reveal the buried AGN components in many more submillimeter sources. In contrast, the X-ray-absorbed QSOs found in the hard-spectrum *ROSAT* survey may be caught at the earliest evolutionary stage readily accessible to conventional X-ray and optical surveys; flourishing and youthful, they may only just be emerging from the obscuring gaseous cocoons of their birth.

The JCMT is operated on behalf of the Particle Physics and Astronomy Research Council of the United Kingdom, the Netherlands Organization for Scientific Research, and the National Research Council of Canada. F. J. C. acknowledges financial support by the Spanish Ministerio de Ciencia y Tecnología, under grant ESP2003-00812.

## REFERENCES

- Alexander, D. M., et al. 2003, *AJ*, 125, 383  
 Antonucci, R. 1993, *ARA&A*, 31, 473  
 Barger, A. J., Cowie L. L., Bautz, M. W., Brandt, W. N., Garmire, G. P., Hornschemeier, A. E., Ivison, R. J., & Owen, F. N. 2001, *AJ*, 122, 2177  
 Boyle, B. J., Shanks, T., Croom, S. M., Smith, R. J., Miller, L., Loaring, N., & Heymans, C. 2000, *MNRAS*, 317, 1014  
 Boyle, B. J., Wilkes, B. J., & Elvis, M. 1997, *MNRAS*, 285, 511  
 Comastri, A., Setti, G., Zamorani, G., & Hasinger, G. 1995, *A&A*, 296, 1  
 Croom, S. M., Schade, D., Boyle, B. J., Shanks, T., Miller, L., & Smith, R. J. 2004, *ApJ*, 606, 126  
 Dunlop, J. S., McLure, R. J., Kukula, M. J., Baum, S. A., O'Dea, C. P., & Hughes, D. H. 2003, *MNRAS*, 340, 1095  
 Elvis, M., et al. 1994, *ApJS*, 95, 1  
 Fabian, A. C. 1999, *MNRAS*, 308, L39  
 Franceschini, A., Hasinger, G., Miyaji, T., & Malquori, D. 1999, *MNRAS*, 310, L5  
 Gehrels, N. 1986, *ApJ*, 303, 336  
 Gilli, R., Salvati, M., & Hasinger, G. 2001, *A&A*, 366, 407  
 Griffiths, R. E., Georgantopoulos, I., Boyle, B. J., Stewart, G. C., Shanks, T., & Della Ceca, R. 1995, *MNRAS*, 275, 77  
 Ivison, R. J., et al. 2002, *MNRAS*, 337, 1  
 Kukula, M. J., Dunlop, J. S., McLure, R. J., Miller, L., Percival, W. J., Baum, S. J., & O'Dea, C. P. 2001, *MNRAS*, 326, 1533  
 Mainieri, V., Bergeron, J., Hasinger, G., Lehmann, I., Rosati, P., Schmidt, M., Szokoly, G., & Della Ceca, R. 2002, *A&A*, 393, 425  
 Mason, K. O., et al. 2000, *MNRAS*, 311, 456  
 McHardy, I. M., et al. 1998, *MNRAS*, 295, 641  
 Merritt, D., & Ferrarese, L. 2001, *MNRAS*, 320, L30  
 Miyaji, T., Hasinger, G., & Schmidt, M. 2001, *A&A*, 369, 49  
 Page, M. J., Mason, K. O., McHardy, I. M., Jones, L. R., & Carrera, F. J. 1997, *MNRAS*, 291, 324  
 Page, M. J., Mittaz, J. P. D., & Carrera, F. J. 2000, *MNRAS*, 318, 1073  
 ———. 2001a, *MNRAS*, 325, 575  
 Page, M. J., Stevens, J. A., Mittaz, J. P. D., & Carrera, F. J. 2001b, *Science*, 294, 2516  
 Page, M. J., et al. 2003, *Astron. Nachr.*, 324, 101  
 Sanders, D. B., Soifer, B. T., Elias, J. H., Madore, B. F., Matthews, K., Neugebauer, G., & Scoville, N. Z. 1988, *ApJ*, 325, 74  
 Schmidt, M., et al. 1998, *A&A*, 329, 495  
 Setti, G., & Woltjer, L. 1989, *A&A*, 224, L21  
 Silk, J., & Rees, M. J. 1998, *A&A*, 331, L1  
 Stevens, J. A., Page, M. J., Ivison, R. J., Smail, I., & Carrera, F. J. 2004, *ApJ*, 604, L17  
 Stocke, J. T., Morris, S. L., Gioia, I. M., Maccacaro, T., Schild, R., Wolter, A., Fleming, T. A., & Henry, J. P. 1991, *ApJS*, 76, 813  
 Tran, H. D. 2003, *ApJ*, 583, 632  
 Yu, Q., & Tremaine, S. 2002, *MNRAS*, 335, 965  
 Yuan, W., Brinkmann, W., Siebert, J., & Voges, W. 1998, *A&A*, 330, 108